

**INDIAN INSTITUTE OF TECHNOLOGY GOA
GEC CAMPUS, Farmagudi, Ponda, Goa-403401**

CONSTRUCTION & ESTATE MANAGEMENT DIVISION

GSTIN: 30AABAI1653D1ZF

PAN: AABAI1653D

TAN: BLRI08261B

Enquiry No: IITGOA/C&EMD/2019/003

Dt.09/07/2019

NOTICE INVITING QUOTATION

Sealed quotations are invited from approved and eligible contractors for the work as stated below;

Sr.No	Item Description	Unit	Quantity	Rate	Amount
1.	Providing and applying white cement-based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.	M2	250		
2.	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete	M2	450		
3.	Distemping with 1st quality acrylic distemper (ready mixed) having VOC content less than 50 gms/litre, of approved manufacturer, of required shade and colour complete, as per manufacturer's specification. i) Two or more coats on new work	M2	450		
4.	Applying one coat of water thinnable cement primer of approved brand and manufacture on wall surface : i) Water thinnable cement primer	M2	450		
5.	Painting with synthetic enamel paint of approved brand and manufacture to	M2	55		

	give an even shade: i) Two or more coats on new work sqm				
6.	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq. Meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground, all complete as per direction of Engineer-in-Charge. i)With cement mortar 1:4 (1cement: 4 coarse sand)	M2	20		

Terms & Conditions:

- 1) Validity of the quotation should be 60days.
- 2) The work should be completed within a stipulated time of 15 days.
- 3) Scaffolding hiring and installation should be included in the work.
- 4) The work shall be carried out strictly in accordance with the terms, conditions and specifications as per CPWD norms, in the approved workmanlike manner and as per standard practice.
- 5) Materials required for satisfactory completion of work shall be of approved quality, make, grade etc. and of/or confirming to the Indian Standard Specifications(Latest revision) wherever applicable and approved by the Engineer-in-charge.
- 6) Payment will be done on satisfactory completion of the work.
- 7) For any query you may contact us on 7798673061; sankesh@iitgoa.ac.in
- 8) You are requested to send the sealed quote directly to the Chief Engineer, IIT Goa, Gec Campus, Farmagudi, Ponda, Goa- 403401 on or before 12th July 2019.